



**EMBU COUNTY GOVERNMENT**

Date 17/04/2023

**REF: ADDENDUM NOTICE FOR ROAD MAINTENANCE TENDERS**

This is to notify all tenderers of **addendum no. 01,02 and 03** for the following tender documents uploaded on **12<sup>th</sup> April 2023** for road projects funded by **County Revenue Fund**

**ADDENDUM 01**

**1. RE- ADVERTISEMENT OF MURRAMING OF SIAKAGO TOWN ROADS IN NTHAWA WARD and 2. RE- ADVERTISEMENT OF MAINTENANCE OF MUCHONOKE - KIARWARA ROAD IN NTHAWA WARD**

**NEGOTIATION NO: 1228864-2022/2023 ADVERTISED ON 12<sup>TH</sup> APRIL 2023**

OMIT "pages 85 to pages 90" in the tender document and replace with **ADDENDUM 1 "pages 1 to page 6"**

**ADDENDUM 02**

**1. RE- ADVERTISEMENT OF GRADING AND MURRAMING OF NGANDI KWA KIVUVA - MBONZUKI ROAD IN MWEA WARD and 2. RE- ADVERTISEMENT OF GRADING AND MURRAMING OF NGANDI NGANG'A - KYUASINI ROAD IN MWEA WARD**

**NEGOTIATION NO: 1227990-2022/2023 ADVERTISED ON 12TH APRIL 2023**

OMIT "page 88" in the tender document and replace with **ADDENDUM 2 "page 1 of page 1"**

**ADDENDUM 03**


**1. RE-ADVERTISEMENT -MAINTENANCE OF KIGUMO-GITITI -KANGINGA ROAD and 2.RE-ADVERTISEMENT MAINTENANCE OF KARURUMO-KARIRU ROAD IN KYENI SOUTH WARD**

**NEGOTIATION NO: 1228972-2022/2023 ADVERTISED ON 12TH APRIL 2023**

OMIT "page 90" in the tender document and replace with **ADDENDUM 03 "page 1 of page 1"**

This addendum will form part of the evaluation.

The closing date remains **25<sup>th</sup> April 2023 at 11.00am** and opening will be done thereafter at the county board room

  
 Ag. Director Procurement Supply Chain Management  
 For County Secretary,  
 Embu County Government



## BILLS OF QUANTITIES

### MURRAMING OF SIAKAGO TOWN ROADS IN NTHAWA WARD

| Bill no. 1 | General: Office administration/Preliminaries  |        |            |            |            |
|------------|---|--------|------------|------------|------------|
| ITEM       | DESCRIPTION   | UNIT   | QTY        | RATE       | AMOUNT     |
| 1.01       | Provide, erect and maintain a publicity sign board throughout the contract period as directed by the Engineer   | Nr     | 1          | 30,000.00  | 30,000.00  |
| 1.02       | Prime cost sum of 15,000 for material testing for specialised quality control test  | PC SUM | 1          | 15,000.00  | 15,000.00  |
| 1.03       | Extra over item 1.02 above for the contractor's overheads and profits   | %      | 15,000.00  |            |            |
| 1.04       | Allow a prime cost Sum of Kenya shillings Ninety Five Thousand(105,000) Only for attendance upon the Resident Engineer and his staff as directed by the Engineer in accordance with clause 137 of the standard specifications | PC SUM | 1          | 105,000.00 | 105,000.00 |
| 1.05       | Extra over item 1.04 above for the contractor's overheads and profits   | %      | 105,000.00 |            |            |
|            | <b>Total carried forward to summary page</b>  |        |            |            |            |

ADDENDUM NOTICE NO. 01-2022/2023 FOR TENDER NO. 1228864-2022/2023

| Bill no. 8                                   | Culverts and drainage works  |                |     |      |        |
|--|--|----------------|-----|------|--------|
| ITEM   | DESCRIPTION  | UNIT           | QTY | RATE | AMOUNT |
| 08.60.027                                    | Excavate for, provide, lay and joint pipe culvert of 600mm in diameter with surround | M              | 7   |      |        |
| 08.70.001                                    | provide stone pitching including grouting of ratio 1:4 cement to motar.              | M <sup>2</sup> | 13  |      |        |
| <b>Total carried forward to summary page</b> |  |                |     |      |        |

| Bill no. 10                           | Grading and Gravelling  |                |        |      |        |
|---------------------------------------|---|----------------|--------|------|--------|
| ITEM                                  | DESCRIPTION   | UNIT           | QTY    | RATE | AMOUNT |
| 10.50.001                             | Trim with motor grader or heavy towed grader existing carriageway surface to camber, including slopes and ditches without providing watering and compaction(Heavy grading). | M <sup>2</sup> | 24,000 |      |        |
| 10.60.001                             | Prepare for road formation and provide, place spread, shape and compact with watering gravel of not less than CRB 20%.  | M <sup>3</sup> | 1,310  |      |        |
| <b>Total carried to summary sheet</b> |   |                |        |      |        |

ADDENDUM NOTICE NO. 01-2022/2023 FOR TENDER NO. 1228864-2022/2023

| <b>SUMMARY PAGE</b> |  |                           |
|---------------------|--|---------------------------|
| <b>Bill No.</b>     | <b>DESCRIPTION</b>   | <b>TOTAL AMOUNT(KShs)</b> |
| 1                   | General: Office administration/Preliminaries                   |                           |
| 8                   | Culverts and drainage works                                    |                           |
| 22                  | Grading and Gravelling   |                           |
|                     | <b>Sub - Total 1</b>   |                           |
|                     | <b>Add 16% V.A.T</b>   |                           |
|                     | <b>Grand Total Carried forward to form of Tender/Quotation</b> |                           |

## BILLS OF QUANTITIES

| <b>MAINTENANCE OF MUCHONOKE - KIARWARA ROAD IN NTHAWA WARD</b> |  |             |            |             |               |
|--|--|-------------|------------|-------------|---------------|
| <b>Bill no.<br/>1</b>  | <b>General: Office administration/Preliminaries</b>  |             |            |             |               |
| <b>ITEM</b>  | <b>DESCRIPTION</b>   | <b>UNIT</b> | <b>QTY</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 1.01   | Provide, erect and maintain contract signboard throughout the contract period as directed by the engineer  | Nr          | 1          | 30,000.00   | 30,000.00     |
| 1.02   | Allow for attendance upon the Resident Engineer and his staff as directed by the Engineer in accordance with clause 137 of the standard specifications | PC<br>SUM   | 1          | 45,000.00   | 45,000.00     |
| 1.03   | Extra over item 1.02 above for the contractor's profits and overheads  | %           | 45,000.00  |             |               |
| 1.04   | Prime cost sum of 10,000 for material testing for specialised quality control test   | PC<br>SUM   | 1          | 10,000.00   | 10,000.00     |
| 1.05   | Extra over item 1.04 above for the contractor's overheads and profits  | %           | 10,000.00  |             |               |
|  | <b>Total carried forward to summary page</b>   |             |            |             |               |

ADDENDUM NOTICE NO. 01-2022/2023 FOR TENDER NO. 1228864-2022/2023

| Bill no. 4                                   | Site Clearance and Topsoil Stripping  |                |       |      |        |
|--|---|----------------|-------|------|--------|
| ITEM   | DESCRIPTION   | UNIT           | QTY   | RATE | AMOUNT |
| 04.50.004                                    | Cut grass by hand from shoulders, slopes, inlet ditches and side ditches including back slopes, turnouts and culvert outlets( <i>Light bush clearing</i> ). | M <sup>2</sup> | 2,000 |      |        |
| <b>Total carried forward to summary page</b> |   |                |       |      |        |

| Bill no. 5                                   | Earth Works                       |                |     |      |        |
|--|-----------------------------------|----------------|-----|------|--------|
| ITEM   | DESCRIPTION                       | UNIT           | QTY | RATE | AMOUNT |
| 05.70.004                                    | Provide Rockfill to the drifts.   | M <sup>3</sup> | 75  |      |        |
| 05.70.005                                    | Fill in hard material to culverts | M <sup>3</sup> | 30  |      |        |
| <b>Total carried forward to summary page</b> |                                   |                |     |      |        |

ADDENDUM NOTICE NO. 01-2022/2023 FOR TENDER NO. 1228864-2022/2023

| Bill no. 7                                   | Excavation and filling for structures                                |                |     |      |        |
|--|--|----------------|-----|------|--------|
| ITEM   | DESCRIPTION  | UNIT           | QTY | RATE | AMOUNT |
| 07.50.002                                    | Excavate manually in hard material for structures                    | M <sup>3</sup> | 6   |      |        |
| 07.70.004                                    | Provide and place macaferri or equivalent gabion boxes(2m*1m*1m)     | M <sup>2</sup> | 132 |      |        |
| 07.70.005                                    | provide and place rockfill to gabions.                               | M <sup>3</sup> | 24  |      |        |
| 07.50.002a                                   | Excavation mechanically in hard material to remove existing culverts | M <sup>3</sup> | 10  |      |        |
| <b>Total carried forward to summary page</b> |  |                |     |      |        |

| Bill no. 8                                   | Culverts and drainage works  |      |     |      |        |
|--|--|------|-----|------|--------|
| ITEM   | DESCRIPTION  | UNIT | QTY | RATE | AMOUNT |
| 08.60.027                                    | Excavate for, provide, lay and joint pipe culvert of 900mm in diameter with surround | M    | 9   |      |        |
| <b>Total carried forward to summary page</b> |  |      |     |      |        |